


dealing with network message lost




handling lost message: acknowledgements




handling lost message



handling lost message



handling lost message



protocol so far

on sender: until ACK received:

- (re)send frame of data
- wait fixed amount of time for ACK

on receiver: continuously:


- wait for frame of data
- send ACK back

problem

really want to send multiple frames


example: data split in multiple pieces

splitting messages: try 1




reconstructed message:
The meeting is at 12pm.

splitting messages: try 1 — problem 1



splitting messages: try 1 — problem 1



reconstructed message:
The meetingThe meeting is at 12pm.

exercise: other problems?

sending ‘The meeting’, ‘is at 12pm’

what would be received for each of these scenarios?

1. message (instead of acknowledgment) is lost
2. first message from machine A is delayed a long time by network
3. acknowledgment of second message lost instead of first


aside: message delays

long message delays not possible with direct link

but are possible with:


- multiple paths from A to B
- doing this kind of acknowledgment + resending hop-by-hop

splitting messages: try 2




reconstructed message:
The meeting is at 12pm.

splitting messages: try 2 — missed ack




reconstructed message:
The meeting is at 12pm.

splitting messages: try 2 — problem



A thinks: part 0 + part 1 acknowleged!

splitting messages: version 3



sequence numbers

call the 'part' label *sequence number*


- for now: sequence number = message (or *segment*) number
- in TCP: sequence number = byte number

important question: how large can they get?

if we never reuse them — infinite!

so *really* want to reuse them

1-bit sequence number



‘stop and wait’

machine A is only sending one thing at a time

never start sending next thing until after sending previous thing

stop-and-wait exercise (receive, 1)

machine B receives `0: X`

machine B sends `ACK 0`

machine B receives `0: X`

what should machine B do now?

A. send `ACK 0` B. send `ACK 1` C. send nothing

stop-and-wait exercise (receive, 2)

machine B receives `0: X`

machine B sends `ACK 0`

machine B receives `1: X`

what should machine B do now?

A. send `ACK 0` B. send `ACK 1` C. send nothing

stop-and-wait exercise (receive, 3)

machine B receives `0: X`

machine B sends `ACK 0`

machine B receives `1: Y`

machine B sends `ACK 1`

machine B receives `0: X`

what should machine B do now?

A. send `ACK 0` B. send `ACK 1` C. send nothing

stop-and-wait exercise (send, 1)

A trying to send ‘X’, then ‘Y’, then ‘Z’

machine A sends `0: X`

machine A sends `0: X`

machine A receives `ACK 0`

machine A sends `1: Y`

machine A receives `ACK 0`

what should machine A do now?

A. send `0: X` again B. send `1: Y` again

C. send `0: Z` D. something else

stop-and-wait exercise (send, 2)

A trying to send ‘X’, then ‘Y’, then ‘Z’

machine A sends `0: X`

machine A sends `0: X`

machine A receives `ACK 0`

machine A sends `1: Y`

machine A receives `ACK 1`

what should machine A do now?

A. send `0: X` again B. send `1: Y` again

C. send `0: Z` D. something else

stop-and-wait issues

two issues with stop-and-wait:

doesn't use close to full capacity of network

not clear how to set timeouts

looking at metrics

several important metrics we'll care about

(both for this and future topics)

looking at metrics

several important metrics we'll care about

(both for this and future topics)

throughput and *bandwidth* ($\sim$ how much capacity used/available)

latency and *round-trip time* (RTT) ($\sim$ what timeouts needed)

jitter ($\sim$ safety margin for timeouts)

bandwidth / throughput

bandwidth / data rate: maximum rate we can send per unit time

- most commonly measuring the speed of a link

1 gigabit/second = transmit 1 bit / nanosecond


throughput: acheived rate per unit time

- often lower than total bandwidth because of losses
- (we'll give several examples throughout the semester)

latency (1)

latency: time for message: SOURCE $\rightarrow$ DEST


example: 1000 bit message from S to D:



latency (1)

latency: time for message: SOURCE $\rightarrow$ DEST

example: 1000 bit message from S to D:



one bit sent each $1/50\text{M}$ second $= 0.02\ \mu$s


1000 bits take $0.02 \times 1000 = 20\ \mu$s to sent

"transmission delay"

latency (1)

latency: time for message: SOURCE $\rightarrow$ DEST

example: 1000 bit message from S to D:



one bit sent each 1/50M second $= 0.02$ μs

1000 bits take $0.02 \times 1000 = 20$ μs to sent

"transmission delay"


$+ 2.2$ microseconds for bit to go down cable (2.3×10^8 m/s)

"propogation delay"

latency (1)

latency: time for message: SOURCE $\rightarrow$ DEST

example: 1000 bit message from S to D:



one bit sent each 1/50M second $= 0.02$ μs

1000 bits take $0.02 \times 1000 = 20$ μs to sent


"transmission delay"

$+ 2.2$ microseconds for bit to go down cable (2.3×10^8 m/s)

"propogation delay"

total latency of about 22.2 μs


latency (1, ex)



exercise: latency for 20000 bit message from S to D

assume speed of signal through fiber of 2.0×10^8 m/s

latency (1, ex)



exercise: latency for 20000 bit message from S to D

assume speed of signal through fiber of 2.0×10^8 m/s

latency (1, ex)



exercise: latency for 20000 bit message from S to D


assume speed of signal through fiber of 2.0×10^8 m/s

latency (2)

example: 1000 bit packet from S to D

assume when message is received:

- 5 other 1000-bit packets in queue; no extra bits between packets
- no other switch processing time



S to switch, switch to D: 22.2 μs (transmit+propogate delay)

within switch: wait $20 \times 5 = 100$ μs for 5 other packets ($20\mu s = 1$ packet transmit delay)

- "queueing delay"


total latency: $22.2 + 100 + 22.2 = 144.4$ microseconds

latency (2)

example: 1000 bit packet from S to D

assume when message is received:

- 5 other 1000-bit packets in queue; no extra bits between packets
- no other switch processing time



S to switch, switch to D: 22.2 μs (transmit+propogate delay)

within switch: wait $20 \times 5 = 100$ μs for 5 other packets ($20\mu s = 1$ packet transmit delay)

- "queueing delay"


total latency: $22.2 + 100 + 22.2 = 144.4$ microseconds

latency (2)

example: 1000 bit packet from S to D

assume when message is received:

- 5 other 1000-bit packets in queue; no extra bits between packets
- no other switch processing time



S to switch, switch to D: 22.2 μs (transmit+propogate delay)

within switch: wait $20 \times 5 = 100$ μs for 5 other packets ($20\mu s = 1$ packet transmit delay)

- "queueing delay"


total latency: $22.2 + 100 + 22.2 = 144.4$ microseconds

latency (2)

example: 1000 bit packet from S to D

assume when message is received:

- 5 other 1000-bit packets in queue; no extra bits between packets
- no other switch processing time



S to switch, switch to D: 22.2 μs (transmit+propogate delay)

within switch: wait $20 \times 5 = 100$ μs for 5 other packets ($20\mu s = 1$ packet transmit delay)

- "queueing delay"

round trip time

round-trip-time (RTT): time for message:
SOURCE $\rightarrow$ DEST $\rightarrow$ SOURCE

much easier to measure than one-way latency

typically how we'll set latency

jitter

variation in latency

most commonly from changing queuing delays





Figure 20 from Section 1.5 of *Computer Networks: A Systems Approach* (6th ed) (Peterson and Davie)

measuring round-trip time (1a)


```
charles@reisst14$ ping 1.1.1.1
PING 1.1.1.1 (1.1.1.1) 56(84) bytes of data.
64 bytes from 1.1.1.1: icmp_seq=1 ttl=52 time=13.8 ms
64 bytes from 1.1.1.1: icmp_seq=2 ttl=52 time=15.0 ms
64 bytes from 1.1.1.1: icmp_seq=3 ttl=52 time=12.5 ms
64 bytes from 1.1.1.1: icmp_seq=4 ttl=52 time=12.3 ms
64 bytes from 1.1.1.1: icmp_seq=5 ttl=52 time=13.5 ms
64 bytes from 1.1.1.1: icmp_seq=6 ttl=52 time=12.5 ms
64 bytes from 1.1.1.1: icmp_seq=7 ttl=52 time=13.3 ms
64 bytes from 1.1.1.1: icmp_seq=8 ttl=52 time=13.2 ms
64 bytes from 1.1.1.1: icmp_seq=9 ttl=52 time=13.3 ms
64 bytes from 1.1.1.1: icmp_seq=10 ttl=52 time=14.1 ms
^C
--- 1.1.1.1 ping statistics ---
10 packets transmitted, 10 received, 0% packet loss, time 9014ms
rtt min/avg/max/mdev = 12.273/13.343/15.024/0.786 ms
```

measuring round-trip-time (1b)



No.	Time	Source	Destination	Protocol	Length	Info
17	2.766137597	172.25.188.87	1.1.1.1	ICMP	98	Echo (ping) request id=0x0002, seq=1/256, ttl=
18	2.779916793	1.1.1.1	172.25.188.87	ICMP	98	Echo (ping) reply id=0x0002, seq=1/256, ttl=
28	3.768363948	172.25.188.87	1.1.1.1	ICMP	98	Echo (ping) request id=0x0002, seq=2/512, ttl=
29	3.783346606	1.1.1.1	172.25.188.87	ICMP	98	Echo (ping) reply id=0x0002, seq=2/512, ttl=
59	4.769791044	172.25.188.87	1.1.1.1	ICMP	98	Echo (ping) request id=0x0002, seq=3/768, ttl=
60	4.782213735	1.1.1.1	172.25.188.87	ICMP	98	Echo (ping) reply id=0x0002, seq=3/768, ttl=
73	5.771827936	172.25.188.87	1.1.1.1	ICMP	98	Echo (ping) request id=0x0002, seq=4/1024, ttl
74	5.784055865	1.1.1.1	172.25.188.87	ICMP	98	Echo (ping) reply id=0x0002, seq=4/1024, ttl
79	6.773358205	172.25.188.87	1.1.1.1	ICMP	98	Echo (ping) request id=0x0002, seq=5/1280, ttl
80	6.786831460	1.1.1.1	172.25.188.87	ICMP	98	Echo (ping) reply id=0x0002, seq=5/1280, ttl
81	7.775177274	172.25.188.87	1.1.1.1	ICMP	98	Echo (ping) request id=0x0002, seq=6/1536, ttl
82	7.787654160	1.1.1.1	172.25.188.87	ICMP	98	Echo (ping) reply id=0x0002, seq=6/1536, ttl
85	8.776273952	172.25.188.87	1.1.1.1	ICMP	98	Echo (ping) request id=0x0002, seq=7/1792, ttl
86	8.789562086	1.1.1.1	172.25.188.87	ICMP	98	Echo (ping) reply id=0x0002, seq=7/1792, ttl
93	9.777262659	172.25.188.87	1.1.1.1	ICMP	98	Echo (ping) request id=0x0002, seq=8/2048, ttl
94	9.790425188	1.1.1.1	172.25.188.87	ICMP	98	Echo (ping) reply id=0x0002, seq=8/2048, ttl
110	10.778251280	172.25.188.87	1.1.1.1	ICMP	98	Echo (ping) request id=0x0002, seq=9/2304, ttl
119	10.791477471	1.1.1.1	172.25.188.87	ICMP	98	Echo (ping) reply id=0x0002, seq=9/2304, ttl
120	11.779834642	172.25.188.87	1.1.1.1	ICMP	98	Echo (ping) request id=0x0002, seq=10/2560, tt
121	11.793858285	1.1.1.1	172.25.188.87	ICMP	98	Echo (ping) reply id=0x0002, seq=10/2560, tt

measuring round-trip-time (1c)



non-ICMP pings (1)

```
HPING www (enp0s31f6 128.143.67.8): NO FLAGS are set, 40 headers + 0 data
len=46 ip=128.143.67.8 ttl=63 DF id=0 sport=0 flags=RA seq=0 win=0 rtt=3.5
len=46 ip=128.143.67.8 ttl=63 DF id=0 sport=0 flags=RA seq=1 win=0 rtt=3.2
len=46 ip=128.143.67.8 ttl=63 DF id=0 sport=0 flags=RA seq=2 win=0 rtt=7.1
len=46 ip=128.143.67.8 ttl=63 DF id=0 sport=0 flags=RA seq=3 win=0 rtt=6.8
len=46 ip=128.143.67.8 ttl=63 DF id=0 sport=0 flags=RA seq=4 win=0 rtt=6.5
len=46 ip=128.143.67.8 ttl=63 DF id=0 sport=0 flags=RA seq=5 win=0 rtt=6.2
len=46 ip=128.143.67.8 ttl=63 DF id=0 sport=0 flags=RA seq=6 win=0 rtt=5.8
len=46 ip=128.143.67.8 ttl=63 DF id=0 sport=0 flags=RA seq=7 win=0 rtt=5.4
len=46 ip=128.143.67.8 ttl=63 DF id=0 sport=0 flags=RA seq=8 win=0 rtt=5.0
len=46 ip=128.143.67.8 ttl=63 DF id=0 sport=0 flags=RA seq=9 win=0 rtt=4.7
^C
--- www hping statistic ---
10 packets transmitted, 10 packets received, 0% packet loss
round-trip min/avg/max = 3.2/5.4/7.1 ms
```

non-ICMP pings (2)

No.	Time	Source	Destination	Protocol	Length	Info
1	0.000000000	128.143.71.27	128.143.67.8	TCP	54	1385 → 0 [<None>] Seq=1 Win=512 Len=0
2	0.000228953	128.143.67.8	128.143.71.27	TCP	60	0 → 1385 [RST, ACK] Seq=1 Ack=1 Win=0 Len=0
3	1.000254996	128.143.71.27	128.143.67.8	TCP	54	1386 → 0 [<None>] Seq=1 Win=512 Len=0
4	1.000555183	128.143.67.8	128.143.71.27	TCP	60	0 → 1386 [RST, ACK] Seq=1 Ack=1 Win=0 Len=0
5	2.000547949	128.143.71.27	128.143.67.8	TCP	54	1387 → 0 [<None>] Seq=1 Win=512 Len=0
6	2.000861315	128.143.67.8	128.143.71.27	TCP	60	0 → 1387 [RST, ACK] Seq=1 Ack=1 Win=0 Len=0
7	3.000765651	128.143.71.27	128.143.67.8	TCP	54	1388 → 0 [<None>] Seq=1 Win=512 Len=0
8	3.000975736	128.143.67.8	128.143.71.27	TCP	60	0 → 1388 [RST, ACK] Seq=1 Ack=1 Win=0 Len=0
9	4.000919160	128.143.71.27	128.143.67.8	TCP	54	1389 → 0 [<None>] Seq=1 Win=512 Len=0
10	4.001230544	128.143.67.8	128.143.71.27	TCP	60	0 → 1389 [RST, ACK] Seq=1 Ack=1 Win=0 Len=0
11	5.001235561	128.143.71.27	128.143.67.8	TCP	54	1390 → 0 [<None>] Seq=1 Win=512 Len=0
12	5.001548682	128.143.67.8	128.143.71.27	TCP	60	0 → 1390 [RST, ACK] Seq=1 Ack=1 Win=0 Len=0
13	6.001564520	128.143.71.27	128.143.67.8	TCP	54	1391 → 0 [<None>] Seq=1 Win=512 Len=0
14	6.001886342	128.143.67.8	128.143.71.27	TCP	60	0 → 1391 [RST, ACK] Seq=1 Ack=1 Win=0 Len=0
15	7.001812043	128.143.71.27	128.143.67.8	TCP	54	1392 → 0 [<None>] Seq=1 Win=512 Len=0
16	7.002151624	128.143.67.8	128.143.71.27	TCP	60	0 → 1392 [RST, ACK] Seq=1 Ack=1 Win=0 Len=0
17	8.002159545	128.143.71.27	128.143.67.8	TCP	54	1393 → 0 [<None>] Seq=1 Win=512 Len=0
18	8.002492960	128.143.67.8	128.143.71.27	TCP	60	0 → 1393 [RST, ACK] Seq=1 Ack=1 Win=0 Len=0
19	9.002512076	128.143.71.27	128.143.67.8	TCP	54	1394 → 0 [<None>] Seq=1 Win=512 Len=0
20	9.002826074	128.143.67.8	128.143.71.27	TCP	60	0 → 1394 [RST, ACK] Seq=1 Ack=1 Win=0 Len=0
21	10.002865037	128.143.71.27	128.143.67.8	TCP	54	1395 → 0 [<None>] Seq=1 Win=512 Len=0
22	10.003183918	128.143.67.8	128.143.71.27	TCP	60	0 → 1395 [RST, ACK] Seq=1 Ack=1 Win=0 Len=0

measuring throughput?

```
$ scp test.dat portal.cs.virginia.edu:test.dat
test.dat                          100%   32MB  23.0MB/s   00:01
$ scp portal.cs.virginia.edu:test.dat .
test.dat                          100%   32MB  28.2MB/s   00:01
```

(but might be measuring disk speed instead)

also more specialized tools like `iperf`

- require program to run on both ends

measuring throughput

```
$ iperf -s
------------------------------------------------------------
Server listening on TCP port 5001
TCP window size:  128 KByte (default)
------------------------------------------------------------
[  1] local 128.143.71.87 port 5001 connected with 128.143.71.27 port 5476
[ ID] Interval       Transfer     Bandwidth
[  1] 0.0000-10.0147 sec  1.09 GBytes   934 Mbits/sec
$ iperf -c kytos02 | tee iperf.out
------------------------------------------------------------
Client connecting to kytos02, TCP port 5001
TCP window size: 85.0 KByte (default)
------------------------------------------------------------
[  1] local 128.143.71.27 port 54760 connected with 128.143.71.87 port 500
[ ID] Interval       Transfer     Bandwidth
[  1] 0.0000-10.0256 sec  1.09 GBytes   933 Mbits/sec
```

measuring transmission delay

```
$ ping -s 1400 www -i 0.05 -c 1000 -q
PING www.cs.virginia.edu (128.143.67.8) 1400(1428) bytes of data.
--- www.cs.virginia.edu ping statistics ---
1000 packets transmitted, 1000 received, 0% packet loss, time 50638ms
rtt min/avg/max/mdev = 0.319/0.461/1.222/0.039 ms
$ ping -s 16 www -i 0.05 -c 1000 -q
PING www.cs.virginia.edu (128.143.67.8) 16(44) bytes of data.
--- www.cs.virginia.edu ping statistics ---
1000 packets transmitted, 1000 received, 0% packet loss, time 50995ms
rtt min/avg/max/mdev = 0.156/0.345/1.539/0.068 ms
```

approx. $0.416 - 0.345 = 0.071$ ms delay for $1400 - 16$ extra bytes

with two links in each direction = approx $\frac{0.071}{4} = 0.018$ ms/link

$\frac{1400 - 16\text{byte}}{0.018\text{ms}} \approx 600$ Mbit/sec

very noisy; true value probably 1 Gbit/sec

stop-and-wait performance

stop-and-wait protocol

assuming no packets lost/corrupted

about one packet per round-trip time

example: local ethernet

my home wired network: 0.6 ms round trip time

typical packet has about 1400 bytes $=$ 11200 bits of data

throughput with stop-and-wait:
$11200\text{b}/0.6\text{ms} \approx 19000\text{b}/\text{ms} = 19\ 000\ 000\text{b}/\text{s} = 19\text{Mbit}/\text{s}$

available bandwidth is about 1 Gbit/s

example: local ethernet


my home wired network: 0.6 ms round trip time

typical packet has about 1400 bytes = 11200 bits of data

throughput with stop-and-wait:
$11200\text{b}/0.6\text{ms} \approx 19000\text{b}/\text{ms} = 19\ 000\ 000\text{b}/\text{s} = 19\text{Mbit}/\text{s}$

available bandwidth is about 1 Gbit/s


sending two at a time




key idea: always have two in flight

send next when previous ack'd

timeouts per message




sending three at a time




choose "window size" to have in flight

send when previous acknowledged


sender window tracking




sender window tracking




sender window tracking



sender window tracking



sender window tracking



exercise 1: out-of-bounds ACK

last ACK recv'd (LAR)	10
last frame sent (LFS)	15
send window size (SWS)	5

what probably happened if we receive an ACK for...

9? 10? 13? 16?

A. only possible if network reorders frames

B. only possible from undetected frame corruption

C. lost ACK for frame ≤ 10

D. lost ACK for frame > 10

E. lost frame 11

F. resent frame from timeout

exercise 2: sender logic

last ACK recv'd (LAR)	10
last frame sent (LFS)	15
send window size (SWS)	5

In this case, there's a timeout that will trigger frame 13 to be resent. If still active, this timeout should be cancelled upon ...

A. receiving ACK 12 B. receiving ACK 13

C. receiving ACK 14 D. sending frame 16

exercise 3a: new data

last ACK recv'd (LAR)	4
last frame sent (LFS)	6
send window size (SWS)	5

if we compute a new frame of data with sequence number 7 to eventually send, we should

A. send it now, advancing LFS
B. wait until we get an ACK for 5 or 6 to send it
C. wait until we get an ACK for 6 to send it
D. wait until the frame with sequence number 6 is resent to send it D. so

exercise 3b: new data

last ACK recv'd (LAR)	4
last frame sent (LFS)	8
send window size (SWS)	4

if we compute a new frame of data with sequence number 9 to eventually send, we should

A. send it now, advancing LFS
B. wait until we get an ACK for 5 or 6 to send it
C. wait until we get an ACK for 6 to send it
D. decline to accept the data because we will never be able to send it
E. something else

sender logic summarized

track variables:

- LFS (last frame sent)
- LAS (last ACK recv'd)
- SWS (send window size)


when receiving ACK $LAR < X \leq LFS$:

- LAR $\leftarrow X$
- clear any timers to resend frames $\leq X$

whenever SWS [send window size] $>$ LFS - LAR *and* data for frame LFS $+ 1$ is available:

- send frame LFS $+ 1$
- set timer to resend frame LFS $+ 1$
- LFS $\leftarrow$ LFS $+ 1$


receiver window tracking




= frame of data with sequeunce number X

(LFR)
last frame recv'd*


(LAF)
last accepted frame




receiver window tracking




receiver window tracking



receiver window tracking



receiver window tracking



receiver logic summarized

track variables:

- LFR (last frame recv'd) — excludes frames after a missing frame
- LAS (last accepted frame)
- RWS (receive window size)

when receiving frame $LFR < X \leq LAS$:


LFR $\leftarrow$ (first missing frame after LFR) - 1

- only advances if X = LFR
- could advance by more than one if frames previously out of order

LAS $\leftarrow$ LFR + RWS

- only advances if X = LFR


simple network model



simulator from upcoming assignment

command line `--delay 1 --bandwidth-forward 10 --bandwidth-backward 100 --buffer 30`

exercise: forward latency




minimum latency = 1 time unit


exercise: maximum latency?

A. 1 time unit B. 1.1 time unit C. 1.2 time unit
C. 1.4 time unit D. 1.9 time unit E. 2.0 time unit
F. 2.1 time unit G. something else


throughput and window size




packet transit time



packet transit time



packet transit time



filling the pipe


round-trip time of 2 time units


from send data to receive ACK (assuming no queuing delay)

can send 10 data frames per time unit


= can send 20 data frames while waiting for ACK


filling the pipe






filling the pipe





filling the pipe



sliding windows solve...

reliability on unrelaible link

congestion control

keep network from being overloaded
...by having window sizes set correctly

flow control

keep sender from getting too far ahead of sender
...by having window sizes set correctly

sequence number wraparound

protocol so far requires arbitrarily large sequence numbers


- doing $<$ and $>$ checks on sequence number, so they need to increase

would like to use smaller sequence numbers


- think: transferring multi-gigabyte file

question: what goes wrong when we reuse sequeunce numbers?


sender/receiver desync: missing ACKs




sender/receiver desync: missing ACKs




sender/receiver desync: missing ACKs




wraparound


machine A
machine B
0: "The "
1: "meeting"
got up to 0
got up to 1
2: "is"
3: "at"
got up to 2
got up to 3
0: "12pm"
got up to 0


loss and resend?



very bad reordering



possible reason



sequence numbers in practice

TCP tries to assume 120 second "maximum segment lifetime"

segment = TCP's name for a packet

original TCP used 32-bit sequence number identifying *byte* number (not segment number)

problem: means wraparound happens on modern (Gigibit+) links in seconds!

sequence numbers in practice

TCP tries to assume 120 second "maximum segment lifetime"

- segment = TCP's name for a packet


original TCP used 32-bit sequence number identifying *byte* number (not segment number)

problem: means wraparound happens on modern (Gigibit+) links in seconds!

workaround: add *additional* 32-bit timestamp field


- used to detect/discard duplicates
- can also be used to set timeouts and/or window sizes

missing messages?



question: what should receiver do with sequence number 2?


missing messages?



question: what should receiver do with sequence number 2?

one idea: ignore it?

missing messages?




question: what should receiver do with sequence number 2?


one idea: ignore it?

better idea: send something back to sender

better idea: always ACK



better idea: always ACK



only ACK x if everything up to and including x received

intuition: ACK tells sender where to start sending more

fast retransmit

if large window + data packet 2 is lost, then sender will see

ACK 0, ACK 1, ACK 1, ACK 1, ACK 1, ACK 1

duplicate ACKs indicate missing packet 2

shouldn't wait for timeout

fast retransmit

if large window + data packet 2 is lost, then sender will see

ACK 0, ACK 1, ACK 1, ACK 1, ACK 1, ACK 1

duplicate ACKs indicate missing packet 2


shouldn't wait for timeout

→ TCP heuristic: retransmit immediately after ∼3 duplicate ACKs

not 1 duplicate ACK to tolerate some reordering

also some other details (we'll talk later)


multiple missing



duplicate ACK heuristic will quickly resend 1, but not 3

would like to supply better information


multiple missing




duplicate ACK heuristic will quickly resend 1, but not 3

would like to supply better information

selective acknowledgments



selective acknowledgments



selective acknowledgments in TCP

optional feature ("extension") described in RFC 2018

send list of ranges received

typically room for 3 ranges

if more than 3 ranges to report, then:

- include range with most recently received frame
- include other ranges until sent three times

TCP

transmission control protocol (TCP)

implements reliable streams of bytes

similar mechanism to what we've described

TCP extras/differences

bidirectional —

- separate sequence numbers in each direction
- can combine data (from A to B) with acknowledgment (from B to A)

sequence numbers are byte numbers —


- can retransmit data in different sized packets
- sequence numbers = index of *first byte* sent
- acknowledgment numbers = index of *last byte* acknowledged

dynamic/variable window sizes


- we'll discuss strategies later

offical name for packets = *segments*


TCP segment format




TCP segment format




TCP segment format




TCP segment format




TCP segment format




TCP segment format




TCP segment format




TCP segment format



TCP segment format



TCP segment format



exercise: maximum throughput

let's say we have a receiver window size of 65535 bytes

and a round-trip time of 100 ms

if we want to avoid sending data the receiver will reject as outside its window, maximum throughput?

A. around 32kbyte/sec
B. around 64kbyte/sec
C. around 128kbyte/sec
D. around 320kbyte/sec
E. around 640kbyte/sec
F. around 1280kbyte/sec
G. something else

selected TCP options

window size scale factor

- allow receiver window sizes greater than 64k
- needed to get reasonable bandwidth on modern networks


timestamps

- allow figuring out round trip time to estimate timeout
- extend 32-bit sequence number, which is too small for multi-gigabit networks


selective acknowledgements

- allow providing information about 'holes' in received data
- example: I got bytes 1–5000, 6000–7000, 8000–9000
- without it would only say 5000


selected TCP option formats




selected TCP option formats



selected TCP option formats




selected TCP option formats



selected TCP option formats




window scale option:




timestamps:




selected TCP option formats



a TCP connection




a TCP connection




a TCP connection

server+client sequence numbers advance by 1 to indicate where in setup




connection setup, no data transferred


a TCP connection




a TCP connection




a TCP connection




a TCP connection




a TCP connection




first data packet




first data packet




first data packet




first data packet




first data packet




first data packet



first data packet




first data packet



no-operation options used to make TCP header size multiple of 4

sequence numbers graph




reading thigs graph

bottom line = last ack number

notches on bottom line = duplicate acks

red lines = selective ACK info

diff. timing in opposite direction



backup slides